



Test -009 تقرير الفحص غير

Test Report

Department: Standards and Technology /

Testing Laboratories

Division: Construction Laboratories

Sample Designation No: 17/01/17/7651

ALmethalia Company for Green Buildings LLC

رسمى مالم يحمل التوقيع المعتمد وختم القسم

Laboratory: Concrete, Building Components

and Chemical Lab

Lab No.: 621

لا ينسخ التقرير بشكل مجزأ إلا بأخذ موافقة

نتائج الفحص

المفحوصة فقط

تمثل العينة

خطية من الجهة

Azzarqa-Attafeh المصدرة للشهادة

Client

Address

Our Reference No.: (170105)/284/55/1/ 08 79 Type of Sample: (wall panels)*

Sample brought by: brought by client

Date of Receipt: 27/4/2017

Your Reference No .: --

Date: 4/5/2017

Date: 27/4/2017

Date of end Test: 4/5/2017

أي كشط او تعديل يلغي هذا التقرير

Test report is only valid with devisionstamp and signature

Test report shall not be reproduced other than in full, except with the written approval of the issuing

Tests	Result
Examine the thermal conductivity (w/m.c°) at a temperature average (10-20)°c	0.08915
Notes	

Notes:

Dime	nsions
Length (mm)	300
Width (mm)	300
Nominal Thickness (m)	
Actual Thickness (m)	0.0670

- -Test was performed according to as ASTM C 177-13 using the curded Hot plate apparatus.
- -Test duration 24 hour for each sample

*As mentioned by the client.

Lab Head: Eng. Nedal Al-Kouz

Manager: Eng. Eyad K rasneh results relate only to the items tested

party

The test

RSSPMP1302, ISSUE 5, Rev. (1)

Page (1) of (2)

Any erasure or attrition in the report will invalid it









هاتف ۲۰۲۱ م.ب ۱۹۲۸ مان ۱۹۲۸ فاکس ۱۹۲۸ م ۱۹۲۸ مین ۱۹۲۸ عمان ۱۹۹۱ الأردن Tel: +962 6 5344701 Fax: +962 6 5344806 P.O.Box 1438 Amman 11941 Jordan



Testing